

SCHEDULE OF DRAWINGS

BILL OF QUANTITIES (объемы работ)

Nr.	DENOMINATION	NOTE
1	COMMON DATA. SCHEDULE OF ROOMS AND REPAIR/FINISHING WORKS	
2	4th FLOOR PLAN. SECTIONS 1-1, 2-2	
3	FALSE CEILING PLAN. SECTIONS 3-3, 4-4, 5-5.	

SCHEDULE OF ROOMS FINISHING

Nr.	DENOMINATION OF ROOMS	M ²	FLOOR	WALLS	CEILING	TALUZE
			FINISING	FINISING	FINISING	FINISING
1	Staircase	19.40	EXISTING FLOOR	DRY MIX LEVELING. DECORATIVE STUCCO	DRY MIX LEVELING. PAINTING WITH WATER PAINT x 2 LAYERS	DRY MIX LEVELING. DECORATIVE STUCCO
2	Reception area	19.74	EXISTING FLOOR	DRY MIX LEVELING. PAINTING WITH WATER PAINT x 2 LAYERS	DRY MIX LEVELING. PAINTING WITH WATER PAINT x 2 LAYERS	DRY MIX LEVELING. PAINTING WITH WATER PAINT x 2 LAYERS
3	General Service Staff	10.89	EXISTING FLOOR	DRY MIX LEVELING. PAINTING WITH WATER PAINT x 2 LAYERS	DRY MIX LEVELING. PAINTING WITH WATER PAINT x 2 LAYERS	DRY MIX LEVELING. PAINTING WITH WATER PAINT x 2 LAYERS
4	Programme Coordinator office	16.57	EXISTING FLOOR	DRY MIX LEVELING. PAINTING WITH WATER PAINT x 2 LAYERS	DRY MIX LEVELING. PAINTING WITH WATER PAINT x 2 LAYERS	DRY MIX LEVELING. PAINTING WITH WATER PAINT x 2 LAYERS
5	Finance/Admin. office	13.60	EXISTING FLOOR	DRY MIX LEVELING. PAINTING WITH WATER PAINT x 2 LAYERS	DRY MIX LEVELING. PAINTING WITH WATER PAINT x 2 LAYERS	DRY MIX LEVELING. PAINTING WITH WATER PAINT x 2 LAYERS
6	Consultant's room	8.57	EXISTING FLOOR	DRY MIX LEVELING. PAINTING WITH WATER PAINT x 2 LAYERS	DRY MIX LEVELING. PAINTING WITH WATER PAINT x 2 LAYERS	DRY MIX LEVELING. PAINTING WITH WATER PAINT x 2 LAYERS
7	Library/Mecting room	21.33	EXISTING FLOOR	DRY MIX LEVELING. PAINTING WITH WATER PAINT x 2 LAYERS	DRY MIX LEVELING. PAINTING WITH WATER PAINT x 2 LAYERS	DRY MIX LEVELING. PAINTING WITH WATER PAINT x 2 LAYERS
8	Project office	10.50	EXISTING FLOOR	DRY MIX LEVELING. PAINTING WITH WATER PAINT x 2 LAYERS	DRY MIX LEVELING. PAINTING WITH WATER PAINT x 2 LAYERS	DRY MIX LEVELING. PAINTING WITH WATER PAINT x 2 LAYERS
9	WC	4.11	EXISTING FLOOR	EXISTING TILING	DRY MIX LEVELING. PAINTING WITH WATER PAINT x 2 LAYERS	DRY MIX LEVELING. PAINTING WITH WATER PAINT x 2 LAYERS
10	Shower	1.81	EXISTING FLOOR	EXISTING TILING	DRY MIX LEVELING. PAINTING WITH WATER PAINT x 2 LAYERS	DRY MIX LEVELING. PAINTING WITH WATER PAINT x 2 LAYERS
11	Corridor	17.10	EXISTING FLOOR	DRY MIX LEVELING. PAINTING WITH WATER PAINT x 2 LAYERS	EXISTING FALSE CEILING "ARMSTRONG"	DRY MIX LEVELING. PAINTING WITH WATER PAINT x 2 LAYERS

LOT I

Офисные помещения

ПОТОЛКИ

1	Снятие обшивки из г/картона	m2	11,5
2	Обшивка потолка по сущ каркасу	m2	11,5
3	Заделка швов сеткой отдельн местами	m2	34
4	Шпатлевка швов	m2	34
5	Грунтовка потолков Tufigrunt	m2	107
6	Шпатлевка	m2	107
7	Грунтовка перед покраской "tufigrunt"	m2	107
8	Покраска водоземulsion за 2 раза	m2	107

СТЕНЫ И ПЕРЕГОРОДКИ

1	Ремонт штук-ки капитальн стен и откосов отд мест	m2	10
2	Снятие старой краски	m2	24
3	Зашивка швов в гипсокарт перегородках сеткой	m2	11
4	Шпаклевка в метсах заделки швов	m2	11
5	Грунтовка стен перегородок гипсокартон	m2	292
6	Шпаклевка	m2	292
7	Покраска стен и перегород водоземulsion за 2 раза	m2	292

РАЗНЫЕ РАБОТЫ

1	Демонтаж и монтаж панелей -отбойники	мп	25
2	Демонтаж и монтаж радиаторов	шт	9
3	Демонтаж и монтаж светильников	шт	18
4	Покрытие пола пленкой	m2	150
5	Уборка мусора ,выноска и вывозка	тн	3

LOT II

Лестничная клетка

1	Демонтаж витража	m2	8,82
2	Монтаж витража из алюминия	m2	8,82
3	Демонтаж и монтаж поручня	мп	3,1
4	Устр-во лесов	m2	48
5	Снятие старой шт-ки местами	m2	4
6	Грунтовка стен глубокого проникн	m2	8,4
7	ремонт шт-ки стен отд местами	m2	4
8	расчистка трещин с послед заделкой	m2	16
9	Снятие подшивки потолка	m2	3
10	Подшивка потолка гипсокартоном	m2	3
11	наклейка сетки на потолок	m2	3
12	шпатлевка швов	m2	3
13	грунтовка потолка	m2	21
14	шпатлевка потолка	m2	21
15	Грунтовка перед покраской	m2	21
16	Грунтовка стен	m2	60
17	Шпатлевка стен по сетке	m2	60
18	Грунтовка под ТИНК	m2	60
19	Штук-ка ТИНК	m2	60
20	Покраска потолка	m2	21
21	Покрытие пленкой поверхность пола и ступеней	m2	50
22	Уборка ,вынос и вывоз мусора	тн	1,5

INVESTOR: UNITED NATIONS DEVELOPMENT PROGRAMME	Selective Repairs of UN House 131, 31 August 1989 str., Chisinau RM	A		
	LOT I: UNFPA premises (4th floor, UN House)	STAGE	SHEET	SHEETS
	LOT 2: Common areas of the UN House (ceiling, corridor and stairs on the 4th floor)	P	1	3
	COMMON DATA. SCHEDULE OF ROOMS REPAIR/FINISHING WORKS			